


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

CORRECTED
WELL PLUGGING RECORD

Meade County. Sec. 15 Twp. 33 Rge. (E) 30 (W)
Location as "NE/CNW/SW" or footage from lines. C SE SE
Lease Owner Musgrove Drilling Company
Lease Name WILLIAMS Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed December 31, 19 61
Application for plugging filed January 29, 19 62
Application for plugging approved January 31, 19 62
Plugging commenced February 3, 19 62
Plugging completed February 5, 19 62
Reason for abandonment of well or producing formation Dry



If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5877 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1588'	None
				4-1/2"	5865'	2505'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well had cement plug from 3,000' to 5650'.
Pulled 4-1/2" casing. Mudded hole to 500'
Set 10' rock bridge to 490', ran 25 sx cement at 490'. Mudded to 40' and set 10' rock bridge to 30'. Ran 10 sx cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
A. L. Abercrombie (employee of owner) for (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of February, 19 62

Leah Faye Hefke
Leah Faye Hefke
Notary Public.

My commission expires June 16, 1963



WILLIAMS NO 1
Panhandle Development Company, Inc.
Section 15-33s-30w
Meade County, Kansas

Casing Record:

Commenced: 12-03-61
Completed: 12-31-61

Ran 52 joints of 8 5/8" O.D. new 24# casing, set at 1588.37' R.B. Cemented with 550 sacks lite wate, 3% CC and 300 sacks Sunset cement. Ran 183 joints 4 1/2" casing, set @ 5862' K. B. cemented bottom stage with 150 sacks salt cement, cemented top stage with 125 sacks salt cement D.V. collar set at 3262'.

Formation:

Formation:	From	To
Top Soil & Clay	0	425
Sand & Clay	425	625
Red Bed	625	880
Red Bed & Gyp	880	1045
Red Bed & Sand	1045	1365
Red Bed & Shale	1365	1590
Shale & Anhydrite	1590	2150
Lime & Shale	2150	2540
Lime	2540	2818
Chalky Lime	2818	2925
Lime & Shale	2925	3503
Lime	3503	4359
Lime	4359	4403
Lime & Shale	4403	4747
Lime	4747	4781
Lime & Shale	4781	4845
Lime	4845	4984
Lime & Shale	4984	5038
Lime	5038	5164
Lime & Shale	5164	5691
Shale, Lime & Sand	5691	5740
Sand & Shale	5740	5852
Lime & Shale	5852	5875

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1962
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas)
County of Kansas) SS

I Hereby affirm that the above and foregoing is a true and correct copy of the log of the Williams No 1 well, located C-SE-SE of Section 15-33s-30w, Meade County, Kansas.

McCLELLAN DRILLING COMPANY

by [Signature]

Subscribed and sworn to before me a notary public this 2nd day of January, 1962.

[Signature]
Notary Public

My Commission Expires:
Sept. 26, 1965