

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Armentrout

WELL NUMBER A # 1

SW NE Ft. from S Section Line

Ft. from E Section Line

SEC. 16 TWP. 33S RGE. 30W (E) or (W)

COUNTY Meade

Date Well Completed 7/2/53

Plugging Commenced 12-4-90

Plugging Completed 12-6-90

LEASE OPERATOR Berexco Inc.

ADDRESS 970 Fourth Financial Ctr. Wichita, Ks. 67202

PHONE (316) 265-3311 OPERATORS LICENSE NO. 05363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Lacy

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation MORROW Depth to Top 5721 Bottom 5731 T.D. 5910

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8	635	0
				9 5/8	2670	0
				5 1/2	5830	3120

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

CIBP @ 4530 to 4510 w/2 sks. of cement

Pump 50 sks. of cement from 1670 to 1570

Pump 40 sks. of cement from 650 to 550

Put 10 sks. of cement from 40 to 0 Cut off & cap 9 5/8 4' below ground level
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Evan C. May

(Address) _____

SUBSCRIBED AND SWORN TO before me this 31st day of January, 1991

Johanna S. Dobler
 Notary Public

My Commission Expires: 10/31/94

