

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-119-20390-0000

API NUMBER 119-20390-A

LEASE NAME James A. Hush

WELL NUMBER 1

660 Ft. from S Section Line

4840 Ft. from E Section Line

SEC. 17 TWP. 33S RGE. 30 (X) or (W)

COUNTY MEADE

Date Well Completed 03/19/90

Plugging Commenced 03/19/90

Plugging Completed 03/19/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R. J. PATRICK OPERATING COMPANY

ADDRESS P O BOX 1314, LIBERAL, KS 67905-1314

PHONE#(316) 624-8483 OPERATORS LICENSE NO. 6528

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 03/19/90 (date)

by MIKE R. WILSON (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? YES

Producing Formation -0- Depth to Top -0- Bottom -0- T.D. 5780'

Show depth and thickness of all water, oil and gas formations. SEE GEOLOGIST REPORT ENCLOSED

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
D & A	D & A	D & A	D&A	8 5/8"	1520	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole w/heavy mud and spotted cement through drill pipe. 1st plug @ 1530' w/50 sacks cmt. 2nd plug @ 710' w/30 sacks cmt. 3rd plug @ 40' w/10 sacks cmt. 4th circulated rathole with 15 sacks cmt. 5th plug circulated mousehole w/10 sacks cmt. USED 60/40 POZMIX W/6% GEL BY HALLIBURTON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ZENITH DRILLING COMPANY License No. 5141


Address Fourth Financial Center, 100 N. Broadway, Suite 505, Wichita, KS 67205

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R. J. PATRICK OPERATING COMPANY

STATE OF KANSAS COUNTY OF SEWARD, ss.

R. J. PATRICK: OWNER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. J. Patrick
R. J. PATRICK
(Address) P O Box 1314, Liberal, KS 67905-1314



SUBSCRIBED AND SWORN TO before me this 29th day of MAY, 1990

Jayn Berry
JAYN BERRY: Notary Public

My Commission Expires: 04/04/92