

15-119-20375-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,375

LEASE NAME Burmeister

WELL NUMBER 1

495 Ft. from S Section Line

495 Ft. from E Section Line

SEC. 17 TWP. 33 RGE. 30 ~~XX~~ or (W)

COUNTY Meade

Date Well Completed 1-10-1980

Plugging Commenced 4-29-1991

Plugging Completed 5-2-1991

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R. J. Patrick Operating

ADDRESS P.O. Box 1314, Liberal, Ks. 67901

PHONE# (316) 624-8384 OPERATORS LICENSE NO. 6666

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-29-91 (date)

by Mr. Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5678' Bottom 5685' T.D. 6060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				85/8"	1520'	0'
Production				4 1/2"	6056	2817'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set:
Pump 2 Sks. hulls and 20 sks. cement to 5300' & pressured to 700 lbs. - Pump 50 sks. cement @1850' - Mud to 850' - Pump 50 sks. cement 850' to 700' - Mud to 40' - put bridge and 10 sks. 40' to 3', cut off 8 5/8", 3' below ground & cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CASING PULLING SERVICE License ST 46290 CORPORATION COMMISSION

Address Box F, Sublette, Ks. 67877


RECEIVED
MAY 13 1991

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R. J. Patrick Operating

STATE OF KANSAS COUNTY OF HASKELL, ss.

CONSERVATION DIVISION
Wichita, Kansas

Edgar J. Eves (Employee of Operator) or ~~(XXXXXXXX)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Edgar J. Eves
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1991

Sondra L. Eves
Notary Public

My Commission Expires: 12-6-92