

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20335-0001

LEASE NAME BROMWELL

WELL NUMBER 1

SPOT LOCATION C W/2

SEC. 18 TWP. 33N RGE. 30 (XXX)(W)

COUNTY MEADE

Date Well Completed 10-3-82

Plugging Commenced 6-15-84

Plugging Completed 6-17-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KAISER-FRANCIS OIL COMPANY

ADDRESS P.O. BOX 21468, TULSA, OKLAHOMA 74121-1468

PHONE # (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DISTRICT 1, DODGE CITY, KANSAS

Is ACO-1 filed? YES If not, is well log attached? N/A

Producing formation MORROW Depth to top 5606 bottom 5672 T.D. 5720

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MORROW	OIL	5606	5672	8 5/8	1497	NONE
MARMATON	OIL	5093	5606	4 1/2	5719	2547'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. SET 25 SX CMT PLUG FROM 5644-5250'. DISPL W/90 BBLs MUD. SHOT 4 T/2" & LD 2547'. SPOT 35 SX CMT PLUG FROM 1550-1450'. SPOT 35 SX CMT PLUG FROM 650-550'. SPOT 10 SX CMT PLUG FROM 40-3'. CUT OFF & WELD ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor MIDWEST CASING PULLERS License No. 6497
Address BOX F
SUBLETTE, KANSAS 67877

STATE OF OKLAHOMA COUNTY OF MEADE, ss.

DREW TYLER, ENGINEER

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Drew Tyler

(Address) P.O. BOX 21468

SUBSCRIBED AND SWORN TO before me this 20 day of JUNE, 19 84

Sue Mills
Notary Public SUE MILLS

My Commission expires: 10-4-87

