

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-119-10063-0000 Well was completed on
API NUMBER 10-11-53

LEASE NAME Novinger

WELL NUMBER 706

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 33S RGE. 30W (E) or (W)

COUNTY Meade

Date Well Completed _____

Plugging Commenced 3-10-88

Plugging Completed 3-12-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS 3543 N.W. 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well 10-11-53

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1, Glenn Barlow

Is ACO-1 filed? 10-11-53 Well was completed on
If not, is well log attached? yes

Producing Formation 5290-5310' Depth to Top 5290' Bottom 5310' T.D. 5400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil	5290	5310	13 3/8	673	none
				8 5/8	2705	1214
				5 1/2	5400	2820

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 50 sks. of cement to plug bottom of 8 5/8 from 2730 to 2630

Pump 50 sks. of cement to plug bottom of 13 3/8 from 700 to 600

Put 20 sks. of cement from 40 to 0

Cut off & cap 13 3/8 3' below ground level. KCC Witness: Mr. Glenn Barlow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Bryan Humphries

Engineering Manager

(Address) 3543 N.W. 58th Street, OKC., OK 73112

APR 12 1988

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 88

CONSERVATION DIVISION
Wichita, Kansas

Joyce L. Porter
Notary Public

My Commission Expires: 6-12-88