

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-119-10046-0000

Well was completed on:
 API NUMBER 1-25-52

LEASE NAME Novinger Unit

WELL NUMBER 503

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 26 TWP. 33S RGE. 30 (W)

COUNTY Meade

Date Well Completed 1-25-52

Plugging Commenced 5-21-88

Plugging Completed 5-24-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 14, 1988 (date)

by District #1 (KCC District Agent's Name).

Well was completed on:
 Is ACO-1 filed? 1-25-52 If not, Is well log attached? yes

Producing Formation Marmaton Depth to Top 5274 Bottom 5307 T.D. 5355'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil	5274	5307	12-3/4"	637	
				8-5/8"	2694	
				5-1/2"	5355	2726'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RIH w/5-1/2" CIBP to 5000 & set CIBP. Dumped 2 sx C1 H cmt. on top of plug. Shot 5-1/2" csg. at 2721 where it came loose. Circulated w/60 bbls. 9.0 ppg drilling mud. Spotted 50 sx C1 H cmt. from 2610 to 2710'. Shot 8-5/8" csg. at 1222' where it came loose. POOH w/8-5/8" csg. to 637'. Spotted 50 sx C1 H cmt. from 537' to 637'. Loaded holes w/10 bbls 9.0 ppg drilling mud (if additional description is necessary, use BACK of this form.) to 40'. (over)

Name of Plugging Contractor Sargent's Casing Pullers License No. 6547

Address Box 506, Liberal, KS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1988

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 88

Marsha C. Wilson
 Notary Public

CONSERVATION DIVISION
 WICHITA, KANSAS
 Commission Expires: 4-1-92

Continued

Spotted 20 sx C1 H cmt. from 40 to surface. Cut off 12-3/4" csg. 4' below ground level. Welded on I.D. plate.