

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Meade County, Sec. 26 Twp. 33S Rge. 30 (W)

Location as "NE/CNW%SW%" or footage from lines C SW NW

Lease Owner Cities Service Oil Company

Lease Name Novinger (Novinger Unit) C-4924 Well No. 502

Office Address P. O. Box 1098, Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 20 19 51

Application for plugging filed March 5 19 72

Application for plugging approved March 6 19 72


Plugging commenced April 6 19 72

Plugging completed April 13 19 72

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production August 19 69

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ed Eves

Producing formation Marmaton Depth to top 5272 Bottom 5294 Total Depth of Well 5904 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Marmaton	Oil	5274	5294	13-3/8	664	0
				9-5/8	2688	0
				5-1/2	5370	3244

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

5100' - 5260'	20 sx cement plug
2000' - 5100'	Heavy Mud
1900 - 2000'	40 sx cement plug
40' - 1900'	Heavy Mud
0' 40'	10 sx cement plug

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Toland & Johnston

Address Box 94336, Oklahoma City, Oklahoma 73109

STATE OF KANSAS, COUNTY OF SEWARD, ss.

R. L. Higginbottom (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. L. Higginbottom*

Box 1098, Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of April, 19 72

My commission expires 8-6-74

B. J. McGriff

Notary Public.

P. R. HARRISON, Co. 2  
5114 1/2 Highway 20000-2001  
Wood County, Kansas  
Galveston Shell Corporation

Commenced: April 27, 1951  
 Completed: June 20, 1951

Surface Clay and Sand	0	247	Lime	3955	3971
Sand, Shale, & Clay	247	611	Shale	3971	4219
Bedded	611	700	Broken Lime	4269	4314
Bedded, Anhydrite Streaks	700	1255	Shale	4314	4470
Bedded & Sand	1255	1416	Lime	4470	4559
Bedded & Shells	1416	1469	Lime & Shale	4559	4605
Anhydrite & Shells	1469	1500	Lime	4605	4990
Anhydrite, Lime & Salt	1500	1577	Lime & Shale	4990	5014
Anhydrite & Lime Shells	1577	1703	Shale	5014	5059
Anhydrite & Bedded	1703	1744	Broken Lime	5059	5077
Bedded & Lime Shells	1744	1753	Lime & Shale	5077	5153
Bedded, Anhydrite & Lime Shells	1753	1805	Lime	5153	5169
Bedded, Lime & Salt	1805	1907	Lime & Shale	5169	5192
Bedded, Lime & Shale	1907	1959	Shale & Broken Lime	5192	5205
Bedded & Lime Streaks	1959	1970	Sandy Lime	5205	5228
Anhydrite, Salt & Lime	1970	2040	Lime	5228	5267
Anhydrite & Lime	2040	2088	Lime & Shale	5267	5272
Anhydrite, Lime & Salt	2088	2154	Lime	5272	5284
Anhydrite, Lime Shells	2154	2195	Slate & Broken Lime	5284	5513
Anhydrite, Lime, Chert & Shells	2195	2209	Shale & Broken Lime	5513	5533
Anhydrite & Lime Shells	2209	2279	Lime	5533	5553
Lime, Anhydrite & Shells	2279	2300	Lime & Shale	5553	5580
Anhydrite & Lime Streaks	2300	2375	Broken Lime	5580	5600
Anhydrite, Lime & Salt	2375	2422	Shale	5600	5606
Anhydrite & Lime	2422	2461	Lime & Shale	5606	5636
Anhydrite	2461	2499	Lime	5636	5642
Anhydrite & Lime	2499	2462	Broken Lime	5642	5665
Lime	2462	2483	Lime & Shale	5665	5706
Lime & Anhydrite Hard	2483	2707	Lime	5706	5722
Lime & Shale	2707	2761	Lime & Shale	5722	5828
Lime	2761	2769	Lime	5828	5832
Lime & Chert	2769	2781	Lime & Shale	5832	5904
Lime & Shale	2781	2849	TOTAL DEPTH	5904	
Anhydrite, Lime & Shale	2849	2925			
Lime & Shale	2925	3010			
Lime & Shale Streaks	3010	3061			
Lime	3061	3067			
Dolomite & Lime	3067	3011			
Lime	3011	3376			
Lime & Shale Streaks	3376	3412			
Lime & Shale	3412	3491			
Sandy Lime	3491	3535			
Broken Lime & Shale	3535	3577			
Shale & Lime	3577	3619			
Lime & Shale Streaks	3619	3649			
Lime	3649	3682			
Lime & Shale Streaks	3682	3712			
Lime & Shale broken	3712	3760			
Shale & Lime	3760	3892			
Sandy Lime	3892	3903			
Shale	3903	3955			

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 3 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

CASING RECORD

- Set 13-3/8" Casing @ 664' w/500 sacks
- Set 9-5/8" Casing @ 2483' w/900 sacks
- Set 9-1/2" Casing @ 5370' w/400 sacks

Notarized G-28-51