


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Meade County, Sec. 31 Twp. 33SRge. 30W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW



Locate well correctly on above
Section Plot

Lease Owner First National Oil, Inc.
Lease Name Shelman Well No. 1
Office Address 23 E. 11th, Liberal, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
Date Well completed January 5, 1978
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced January 5, 1978
Plugging completed January 5, 1978
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey of Hays
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5855'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing		0	1549'	8-5/8"	1549'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged Hole w/35 sax @ 1550', 25 sax @ 300',
10 sax 40' to 3' below GL. Job completed @ 6:40 P.M.

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


~~John R. Bartholomew of Sage Drilling Co. (employee of owner) or (owner) or (operator)~~
~~of the above described well~~, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
500 Bitting Bldg., Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 78

Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1978



DRILLERS LOG

SHELMAN NO. 1

CASING RECORD:	OPERATOR:	First National Oil, Inc.	DESCRIPTION:
8-5/8" set @ 1549' w/750 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	NW NW Sec. 31-33S-30W Meade County, Kansas.
TOTAL DEPTH:	COMMENCED:	December 22, 1977	
5855'	COMPLETED:	January 5, 1978	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	875	
Sand & Red Bed	875	1550	
Red Bed	1550	1760	
Red Bed & Sand	1760	2260	
Lime & Shale	2260	2425	
Red Bed & Shale	2425	2635	
Lime & Shale	2635	3535	
Dolomite	3535	3745	
Lime & Shale	3745	4115	
Shale & Lime	4115	4420	
Lime & Shale	4420	4565	
Shale & Lime	4565	4770	
Lime & Shale	4770	5083	
Shale & Lime	5083	5215	
Lime & Shale	5215	5804	Logged Hole; Ran DST#1; D&A.
Lime & Shale	5804	5855	

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1978

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew

Subscribed and sworn to before me this 12th day of January, 1978.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1978.

