

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Meade County, Sec. 32 Twp. 33S Rge. 30W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C N/2 NW

Lease Owner Imperial Oil Company
Lease Name Braden Well No. 1-32

Office Address 720 Fourth Financial Center Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)


Dry Hole

Date Well completed July 14 19 82
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced July 14, 19 82
Plugging completed July 14, 19 82
Reason for abandonment of well or producing formation

-Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 6250'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1540'	8-5/8"	1540'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 1st plug @ 1610' w/50 sax cement, 2nd @ 800' w/20 sax, 3rd @ 40' w/10 sax, 10 sax in rat hole & 10 sax in mouse hole. Job completed @ 7:00 a.m.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Sedgwick, ss.


John R. Bartholomew
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John R. Bartholomew
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19

Louise K. Whitted
Notary Public.

My commission expires



RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1982

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

BRADEN NO. 1-32

CASING RECORD:	OPERATOR: Imperial Oil Company	DESCRIPTION:
8-5/8" set @ 1540' w/800 sax cement	CONTRACTOR: Sage Drilling Co., Inc.	C N/2 NW Section 32-33S-30W Meade County, Kansas
TOTAL DEPTH: 6250'	COMMENCED: June 29, 1982	
	COMPLETED: July 14, 1982	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Red Bed	0	978	
Red Bed & Sand	978	1540	
Red Bed & Shale	1540	2370	
Shale	2370	2700	
Lime & Shale	2700	5200	
Shale & Lime	5200	5296	
Lime & Shale	5296	5500	
Shale & Lime	5500	5596	
Lime & Shale	5596	5624	Ran DST #1
Shale & Lime	5624	5640	
Lime & Shale	5640	5797	Ran DST #2 " DST #3 " DST #4
Shale & Lime	5797	5810	
Lime & Shale	5810	6020	
Shale & Lime	6020	6105	
Lime & Shale	6105	6250	Logged Hole, D & A

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

BY John R. Bartholomew
John R. Bartholomew

Subscribed and sworn to before me this 19th day of July, 1982.

RECEIVED Louise K. Whitted
LOUISE K. WHITTED, STATE NOTARY PUBLIC
STATE CORPORATION COMMISSION
Sedgwick County, Kansas
My Appt. Expires 11-26-82
Louise K. Whitted, Notary Public

JUL 20 1982