

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Well was completed on

15-119-10055-00-00

API NUMBER 7-3-52

LEASE NAME Novinger

WELL NUMBER 701

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 33S RGE. 30 (Star (W))

COUNTY Meade

Date Well Completed 7-3-52

Plugging Commenced 3-15-88

Plugging Completed 3-19-88

LEASE OPERATOR OXY USA Inc.

ADDRESS 3543 N.W. 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 Glenn Barlow

Is ACO-1 filed? Well was completed on 7-3-52 If not, is well log attached? Yes

Producing Formation 5280-5296 Depth to Top 5280 Bottom 5296 T.D. 5367

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil	5280	5296	13 3/8	652	none
				8 5/8	2710	1235
				5 1/2	5367	2710

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 50 sks. of cement to plug bottom of 8 5/8 plug from 2700 to 2600

Pump 50 sks. of cement to plug bottom of 13 3/8 plug from 675 to 575

Put 10 sks. of cement from 40 to 0

Cut off & cap 13 3/8 3' below ground level. KCC Witness: Mr. Glenn Barlow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan D. Humphries

Engineering Manager

(Address) 3543 N.W. 58th Street, OKC, OK 73112

APR 12 1988

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 88

CONSERVATION DIVISION
Wichita, Kansas

James A. Porter
Notary Public

My Commission Expires: 6-12-88