

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Well was completed on

API NUMBER 7-11-52

15-119-10060-00-00

LEASE NAME Novinger

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 703

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 34 TWP. 33S RGE. 30W (~~30E~~) (W)

COUNTY Meade

Date Well Completed 7-11-52

Plugging Commenced 4-27-88

Plugging Completed 4-30-88

LEASE OPERATOR OXY USA Inc.

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 Glenn Barlow

Well was completed on

Is ACO-1 filed? 7-11-52 If not, is well log attached? yes

Producing Formation Marmaton Depth to Top 5300 Bottom 5303 T.D. 5950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil	5300	5303	13 3/8	660	none
				9 5/8	2708	660
				5 1/2	5360	2728

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
CIBP @ 5010 w/2 sks. of cement.

Pump 50 sks. of cement to plug bottom of 9 5/8, plug from 2728 to 2628

Pump 50 sks. of cement to plug bottom of 13 3/8, plug from 660 to 550

Put 20 sks. of cement from 40 to 0 Cut off & cap 13 3/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. REG 6547ED

Address Box 506 Liberal, Kansas 67905-0506

STATE CORPORATION COMMISSION
WICHITA, KANSAS

STATE OF Oklahoma COUNTY OF Oklahoma, ss. JUN 2 1988

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries
3545 N.W. 58th Street

(Address) Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1988

Marsha G. Wilson
Notary Public

My Commission Expires: 4-1-92