

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Well was completed on

API NUMBER 4-1-54

15-119-10056-00-00

LEASE NAME Novinger

TYPE OR PRINT

WELL NUMBER 901

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

660 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 34 TWP. 33 RGE. 30 (E-W)

ADDRESS 3543 N.W. 58th Street, Oklahoma City, OK 73112

COUNTY Meade

PHONE (405) 949-4268 OPERATORS LICENSE NO. 5447

Date Well Completed 4-1-54

Character of Well Oil

Plugging Commenced 2-22-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-26-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow, District #1

Well was completed on

is ACO-1 filed? 4-1-54 If not, is well log attached? yes

Producing Formation 5285-5300' Depth to Top 5285 Bottom 5300' T.D. 5382

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Marmaton	Oil	5285	5300	13 3/8	781	none
				9 5/8	2693	1225
				5 1/2	5380	2820

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 50 sks. of cement to plug bottom of 9 5/8, plug from 2730 to 2630

Pump 50 sks. of cement to plug bottom of 13 3/8, plug from 800 to 700

Put 20 sks. of cement from 40 to 0

Cut off & cap 13 3/8 3' below ground level. KCC Witness: Mr. Glenn Barlow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct. So help me God.

STATE CORPORATION COMMISSION

(Signature) Bryan Humphries

(Address) Engineering Manager  
3543 N.W. 58th Street, QKC 73112

APR 12 1988

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 88

CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires: 6-12-88

Jayce S. Hester  
Notary Public