

API NUMBER 15-175-20272-00-00
 LEASE NAME Graber
 WELL NUMBER 3
4950 Ft. from S/N Line of Section (circle one)
4450 Ft. from E/W Line of Section (circle one)

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company
 ADDRESS P. O. Box 21468
 CITY, STATE, ZIP Tulsa OK 74121-1468
 PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568
 Character of Well Gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION - - NW - NW
 SEC. 7 TWP. 33 S. RGE 31 (E) or (W)
 COUNTY Seward
 Date Well Completed 11/17/75
 Date Plugging Commenced 2/28/02
 Date Plugging Completed 3/5/02

The plugging proposal was approved on 2/28/02 (date)
 by Steve Pfiefer (KCC District Agent's Name)

Is ACO-1 filed? On old form not, is well log attached? n/a

Producing Formation(s) Toronto Depth to Top 4247 Bottom 4283 T.D. 4424

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Toronto	Gas	4247	4283	8 5/8	1539	-0-
				5 1/2	4374	2431

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 4200' w/2 sxs cmt on top to 4180'. Located free-point & cut off 5 1/2" casing @ 2431'. POOH & LD. Circ'd hole w/ mud. Pumped 50 sx cmt plug from 1570'-1420'. Pumped 40 sx cmt plug from 600'-480'. Pumped 10 sx cmt plug from 40'-surface. Cut off & capped 8 5/8" casing 3' below G.L. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc.

License No. 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN to before me this 10th day of March, 19 2002



Wynona Yates
 Notary Public

My Commission Expires 11/16/2003

RECEIVED
 APR 01 2002
 KCC WICHITA

OR