


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail & Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pratt County, Sec. 36 Twp. 27 Rge. 15 (E) (W)
Location as "NE/CNW/SW" or footage from lines. SE NW SE
Lease Owner Braden Deam, Inc.
Lease Name Miller Well No. 1
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2/6/68 19
Plugging completed 2/13/68 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation Depth to top Bottom Total Depth of Well 4702 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	294'	none
				5-1/2"	4647'	2448'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded to 4375' and ran 5 sacks of cement. Checked hole, loaded hole, shot pipe at 2620', 2526', 2429', worked pipe loose and pulled 75 joints of 5 1/2" casing. Set 10' rock bridge at 250' and ran 13 sacks of cement. Bailed hole dry, dumped 12 sacks of cement. Mudded hole to 40', 10' rock bridge and ran 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of February, 1968

My commission expires February 15, 1971

Margaret Melcher
Notary Public.

DRILLER'S LOG

Braden Drilling, Inc. et al
 MILLER #1
 SE NW SE Sec. 36-278-15W
 Pratt County, Kansas

Commenced: May 8, 1961
 Completed: May 26, 1961

Set 8 5/8" at 294' and cemented
 with 300 sacks cement.

Set 5 1/2" casing at 4647' and
 cemented with 200 sacks cement.

TS ~~3900~~
 3900

Sand and gravel	200 ft.
Sand, shale, shells	294
Clay, shale	460
Shale and redbed	945
Anhydrite	975
Shale and redbed	1320
Shale and shells	2065
Lime	2470
Lime and shale	3075
Shale - chalk	3235
Shale and lime	3375
Lime	3435
Shale	3540
Lime and shale	3875
Lime	3995
Lime and shale	4040
Lime	4329
Lime and shale	4371
Lime	4452
Sand	4465
Lime	4477
Lime and shale	4536
Lime	4549
Lime, chert and shale	4595
Lime and chert	4627
Shale	4645
Shale and sand	4694
Lime and shale	4762 T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 5 - 1968
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above
 captioned well, as shown by the daily drilling reports.

F. M. Callaway
 F. M. Callaway

Subscribed and sworn to before me this 21st day of December, 1961.

My commission expires March 21, 1962

Helen Schultz
 Helen Schultz, Notary Public