


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 8 Twp. 28 Rge. (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Graham-Messman-Rinehart Drilling Co.
Lease Name Smith Well No. 1
Office Address 1005 E. Second Street, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 25, 1953
Application for plugging filed August 25, 1953
Application for plugging approved August 25, 1953
Plugging commenced August 25, 1953
Plugging completed August 25, 1953
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4548 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 250 ft. with mud.
Left bottom plug in pipe with 1/2 sk.
hulls under plug and 25 sx. cement
on top of plug. Top plug at 35 ft.
with 10 sx. cement and 1/2 sk. hulls
unter top plug. Mud to surface.

RECEIVED
STATE CORPORATION COMMISSION
SEP - 8 1953
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graham-Messman-Rinehart Oil Company
Address P. O. Box 1033, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. A. Gilliland (employee of owner) ~~not a former operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland
1005 E. Second Street, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of August, 19 53.

My commission expires December 1, 1956
Barbara J. Scott Notary Public.

PLUGGING
FILE SEC. 8 T 28 R 13W
BOOK PAGE 25 LINE 10

SMITH #1

WELL RECORD

Location: SW SW NE, 8-28S-13W
Pratt County, Kansas

Commenced: August 11, 1953

Operator: G-M-R Oil Company

Completed: August 25, 1953

Contractor: G-M-R Oil Company

Elevation: 1896 K.B.

Casing Record: 8-5/8" @ 255' w/161 sx.
cement & 4 c.c.

Production: D & A

LOG

Sand & Clay	93
Shale - Clay	255
Shale	395
Shale	1308
Shale-Shells	1855
Lime - Shale	2035
Lime - Shale	2185
Lime - Shale	2295
Lime - Shale	2470
Shale - Lime	2615
Shale - Lime	2736
Shale Lime	2931
Shale - Lime	3040
Shale - Lime	3120
Shale - Lime	3210
Shale - Lime	3253
Shale - Lime	3353
Shale - Lime	3421
Shale - Lime	3545
Shale - Lime	3712
Shale - Lime	3782
Lime - Shale	3809
Lime (Brown)	3828
Lansing	3862
Lime	3914
Lime	3958
Lime	3977
Lime	4021
Lime	4061
Lime	4100
Lime	4136
Lime	4190
Lime	4194
Lime	4247
Lime	4301
Lime	4340
Lime	4372
Lime - Chert	4409
Lime - Chert	4433
Lime - Chert	4473
Lime - Shale	4504
Lime - Shale	4518
Arbuckle	4537
Arbuckle	4548 T.D.

TOPS

3674 - Douglas Sand (-1778)
3809 - Brown Lime (-1913)
3828 - Lansing (-1942)
4280 - Mississippi Chert (-2364)
4322 - Kinderhook (-2426)
4348 - Viola Chert (-2452)
4419 - Simpson Shale (-2523)
4518 - Arbuckle (-2622)

PLUGGING
 FILE SEC 8 T 28 R 13W
 BOOK PAGE 125 LINE 10

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
 J. A. Gilliland

Subscribed and sworn to before me this 5th day of September, 1953.

My Commission Expires: December 1, 1956

Carroll J. Scott
 Notary Public