


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-077-20068-0000

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Harper County. Sec. 10 Twp. 31 Rge. 7 (E) (W) X  
Location as "NE/CNW%SW%" or footage from lines C SW SE  
Lease Owner Kathol Petroleum, Inc.  
Lease Name Bolles Well No. 1  
Office Address 900 Sutton Place Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_\_\_  
Application for plugging filed 19\_\_\_\_  
Application for plugging approved 19\_\_\_\_  
Plugging commenced 7-15-70 19\_\_\_\_  
Plugging completed 7-18-70 19\_\_\_\_  
Reason for abandonment of well or producing formation  
If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4390 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	249	None
				5 1/2	4384	3690.40

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 23 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved rig to location. Rigged up pole. Set plug at 4350'. Put 2 gallons rock on plug. Started digging cellar. Plugged hole back to 4320' with 30 gallons of sand on the bottom. Finished digging cellar. Rigged up jacks. Dumped 5 sacks of cement on bottom with dump bailer. Worked pipe at 32 inches stretch at 2500 psi. Shot pipe at 3745'. Moved pipe 12 inches. Worked pipe loose. Used big jacks on first 11 joints, changed to small jacks and laid down a total of 90 joints. Loaded up rig. Set plug with 10 feet rock bridge at 240 feet. Filled surface pipe with 4 yards of ready mix concrete. Let pole down and moved rig out to road.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of July, 1970

My commission expires May 27, 1973



(Signature) Alice Hickel  
Notary Public.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 8 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL LOG

COMPANY: KATHOL PETROLEUM, INC.  
 CONTRACTOR: BOWERS DRILLING COMPANY, INC.  
 FARM: Belles #1  
 LOCATION: SW/4 SE/4 Sec. 10-31S-7W  
 Harper County, Kansas  
 COMMENCED: 10-18-68  
 COMPLETED: 10-27-68  
 ELEVATION:

15-077-20068-0000

0 - 90	Sand	8-5/8" casing set at 249' w/200 sacks cement
90 - 250	Red shells	
250 - 1450	Shale	
1450 - 1690	Shale and shells	
1690 - 3960	Lime and shale	
3960 - 4072	Lime	
4072 - 4115	Lime and shale	
4115 - 4260	Lime	
4260 - 4382	Lime and shale	
4382 - 4390	Sand	
4390	T. D.	5 1/2" casing set at 4384' w/100 sacks cement

LOG TOPS:

Heebner	3312'	(-1716)
Douglas	3406'	(-1810)
Stalnaker Sand	3589'	(-1993)
Kansas City	3853'	(-2257)
Base/K.C.	4098'	(-2502)
Cherokee	4251'	(-2655)
Mississippi	4382'	(-2786)
T. D.	4390'	(-2794)

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Belles #1 located SW SE Section 10-31S-7W, Harper County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*  
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, this 4th day of November, 1968.

*Sherry Gish*  
 Sherry Gish, Notary Public

My commission expires June 30, 1971.