

WELL PLUGGING RECORD

15-677-30068-00-01

Give All Information Completely  
Make Required Affidavit

COUNTY Harper SEC. 10 TWP. 31S RGE. 07E/W  
Location as in quarters or footage from lines:

C SE NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Indian Wells oil co  
Lease Name Mather Well No. 1  
Office Address Box 322 Haymarket Mo 67060  
Character of Well (Completed as Oil, Gas or Dry Hole): oil & SWD  
Date Well Completed unknown  
Application for plugging filed  
Plugging commenced 4-12-83  
Plugging completed 5-11-83

Reason for abandonment of well or producing formation

non productive

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Glen Ward

Producing formation Miss Depth to top 4346 bottom 4370 T.D. 4798

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Miss</u>		<u>4345</u>	<u>4375</u>	<u>8 3/4</u>	<u>365</u>	<u>0</u>
<u>Simpson</u>		<u>4740</u>	<u>4798</u>	<u>5 1/2"</u>	<u>4798</u>	<u>504'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Set 5 1/2" Halliburton EZ drill plugs @ 4298. For 2" tubing tried to run through plug could not pull. tubing up spotted 50 sacks cement on top of plug pulled 1,000 feet of tubing to 3298 spotted 50 sacks cement pulled tubing much in hole up to top plug, pumped top plug of 150 sacks 4 7/8 C.C. 16 sacks of gell. cement stayed 16 1/2" back from surface, filled surface to top w/ 4 1/2 yards ready mix cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messel Corp.

STATE OF Kansas COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature)

Renee Green

(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of May, 19 83

Gary D. Stearns  
Gary D. Stearns Notary Public.  
STATE CORPORATION COMMISSION

My Commission expires: August 4, 1984

MAY 13 1983