


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-077-30069-0600 WELL PLUGGING RECORD

Harper County. Sec. 19 Twp. 31 Rge. 9 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW
Lease Owner Beardmore Drilling Company
Lease Name Anthony Well No. 1
Office Address 700 - One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-29 19 65
Application for plugging filed 11-29 19 65
Application for plugging approved 11-29 19 65
Plugging commenced 11-29 19 65
Plugging completed 11-29 19 65
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4638 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand and shale		0	242'	8-5/8"	242'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 0 to 40' - 10 sacks cement
- 40' - wood plug
- 40' to 175' - heavy mud
- 175' to 240' - 25 sacks cement
- 240' - wood plug
- 240' to 4638' - heavy mud

RECEIVED
STATE CORPORATION COMMISSION
DEC 13 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Walters Drilling Co.
Address 510 Orpheum Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Heber Beardmore (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
700 - 120 Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of December, 19 65

My commission expires 7-13-67
Shirley Ann Jackson
Shirley Ann Jackson Notary Public.



15-077-30069-0000

DRILLER'S LOG

COMPANY: BEARDMORE DRILLING CO. & WALTERS DRILLING CO.
 SUITE 700 - ONE TWENTY BUILDING
 WICHITA, KANSAS

WELL NAME: ANTHONY #1
 C NE SW SEC. 19-31S-9W
 HARPER COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
 510 ORPHEUM BUILDING
 WICHITA, KANSAS

ROTARY DRILLING COMMENCED: NOVEMBER 15, 1965
 ROTARY DRILLING COMPLETED: NOVEMBER 29, 1965

ELEVATION: 1722 KB

CASING RECORD: 8 5/8" @ 242' w/ 200 sx. cement

LOG

0 - 70	Sand and Soil
70 - 165	Sand
165 - 243	Red Bed
243 - 865	Shale
865 - 1590	Shale and Shells
1590 - 2425	Shale and Lime
2425 - 2635	Shale and Lime Streaks
2635 - 3015	Shale and Lime
3015 - 3049	Shale, Sand and Lime
3049 - 3725	Lime and Shale
3725 - 3809	Shale and Lime
3809 - 4368	Lime
4368 - 4526	Lime and Shale
4526 - 4541	Lime and Chert
4541 - 4600	Lime and Chert
4600 - 4638	Lime
<u>4638</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 13 1965
 CONSERVATION DIVISION
 WICHITA, KANSAS

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY Robert F. Walters
 ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
 this 7th day of December, 1965.

Juanita M. Green
 Juanita M. Green, Notary Public

My Commission Expires: October 4, 1967