


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

15-077-49050-0000



Locate well correctly on above
Section Plot

Harper County, Sec. 24 Twp. 31 Rge. 9 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NW NE
Lease Owner Pickrell Drlg. Co., Wichita, Kansas 67202
Lease Name Darnes 'B' Well No. # 2
Office Address 705 4th National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed February 7 1956
Application for plugging filed October 1973
Application for plugging approved October 1973
Plugging commenced October 26 1973
Plugging completed October 31 1973
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production July 25 1973
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation Mississippi Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	305	None
				5 1/2"	4446	3309

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

October 26, 1973 Plugged off bottom. Dumped sand to 4300'. Mixed and dumped 5 sx of cement.

October 31, 1973 Plugged off top. Set 10' rock bridge at 260'. Filled 8 5/8" surface casing from 260' to base of cellar with 3000 lb. P.S.I. ready-mix concrete.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1973

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor RUSS CASING PULLING, INC.
Address P. O. Box 1082 : Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF SEDGWICK ss.
Jack Gurley

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack Gurley
705 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of November 1973



My commission expires April 17, 1977

Helen L. Sage
Notary Public.

DEC 29 RECD

GABBERT-JONES DRILLING COMPANY
WICHITA, KANSAS
DRILLERS WELL LOG

DARNES B#2
NE NW NE SEC. 24-31-9W
HARPER COUNTY, KANSAS
COMMENCED 12-9-55
COMPLETED 12-22-55

15-077-19050-0000

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	55	SAND & CLAY	
55	170	RED BED	
170	305	SHALE & SHELLS	RAN 305' OF 8-5/8" CASING CEMENTED @ 305' WITH 250 SACKS CEMENT.
305	1395	SHALE & SHELLS	
1395	1575	ANHYDRITE	
1575	1915	SHALE & LIME	
1915	2040	LIME	
2040	2420	LIME & SHALE	
2420	2620	SHALE & SHELLS	
2620	2945	SHALE & LIME	
2945	2995	SHALE	
2995	3090	LIME	
3090	3300	LIME & SHALE	
3300	3310	SHALE	
3310	3330	LIME	
3330	3425	LIME & SHALE	
3425	3535	LIME	
3535	3590	SHALE & SAND	
3590	3815	LIME	
3815	3890	SHALE & LIME	
3890	3915	LIME	
3915	3970	LIME & SHALE	
3970	4445	LIME	
4445	TD		RAN 4445' OF 5 1/2" CASING, CEMENTED WITH 150 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1973
CONSERVATION DIVISION
Wichita, Kansas

I, C. L. Gabbert CERTIFY THIS LOG TO BE A TRUE AND CORRECT COPY OF THE
DRILLER'S WELL LOG FOR THE WELL DESCRIBED ABOVE.

C. L. Gabbert

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY
AND STATE, ON THIS 28th DAY OF November, 1955, PERSONALLY APPEARED
C. L. Gabbert TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO
EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED
THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN
SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE
DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 11-19-58

Sumner E. Hall
NOTARY PUBLIC