

15-175-21000-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-1
Rev. 6/4/84

AUG 23 1988

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
Wichita, Kansas

API NUMBER 15-175-21,000-0000 (of this well) 8/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Frazier "B" WELL NO. 1 WELL LOCATION C NW NW COUNTY Seward

SEC. 1 TWP. 33S RGE. 33 ~~(S)~~ (W) TOTAL DEPTH 7310' PLUG BACK TD 2689'

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 1541' CEMENTED WITH 700 SACKS

CASING SIZE 5-1/2" SET AT 2689' CEMENTED WITH 420 SACKS

PERFORATED AT 2589-95, 2564-71, 2550-60, 2522-28

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 20 sxs cmt from PSTD-2500, pmp mud and

hulls to 1600', shoot casing off @ freepoint, spot 50 sxs cmt 1450'-1650', pmp mud to 530',
spot 20 sxs cmt 430'-530', pmp mud to 40', spot 10 sxs cmt 40'-0', cut off and cap well 3'
below ground level.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jim Barlow PHONE # (316) 624-6253

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargent's Casing Pullers LICENSE NO. 6547 6/89

ADDRESS Box 506, Liberal, Kansas 67905-0506 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)

DATE: 8/22/88 M. L. Pease, Division Production Manager

①

15-175-21000-0000

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

NOV 23 '88

EXPIRES

August 23, 1988

WELL PLUGGING NOTICE

Frazier "B" #1
C NW NW
Sec. 01-33S-33W
Seward County

Anadarko Petroleum Corporation
P.O. Box 351
Liberal, KS 67905-0351


Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,



Shari Feist
Director
State Corporation Commission

DISTRICT #1 304 W. McArtor, Dodge City, KS 67801 (316) 225-6760