

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20769-00-00
Spot: N2SESE Sec/Twnshp/Rge: 22-34S-21W
1190 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: BARBY-HARPER Well Number: 13-22
County: CLARK Total Vertical Depth: 5110 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

Conductor Pipe: Size 20 feet: 100 8166.08
Surface Casing: Size 8.625 feet: 839 WITH 700 SX CMT
Production: Size 5.5 feet: 4474 WITH 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/17/2003 1:30 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4240' WITH 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 01/17/2003 2:00 PM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4430'. PERFS AT 4307-4308'. SAND TO 4240' WITH 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 900#. SHUT IN PRESSURE 250#.

RECEIVED
JAN 27 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3009' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE 1-28-03

INV. NO. 2003061118

Form CP-20