

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20729-00-00  
Spot: CSEWSE Sec/Twnshp/Rge: 22-34S-21W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: BARBY-HARPER A Well Number: 6-22  
County: CLARK Total Vertical Depth: 4400 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N. TYLER  
WICHITA, KS 67212

Conductor Pipe: Size 20 feet: 90 \$143.00  
Surface Casing: Size 8.625 feet: 840 WITH 600 SX CMT  
Production: Size 4.5 feet: 4362 WITH 150 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/17/2003 12:40 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4242' WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/17/2003 1:10 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4362'. PERFS AT 4292-4304'. SAND TO 4242' WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 450#. SHUT IN PRESSURE 100#.

RECEIVED  
JAN 27 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3430' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE 1-28-03

INV. NO. 2003061118

Form C-21/3