

1-060331

15-025-10106-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed in 1955

C SW NE , SEC. 11 , T 34 S, R 21 W/E
3300 feet from ~~N~~ SE Corner of ~~W~~ section line
1980 feet from ~~W~~ SE Corner of ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5168

Lease Name K.C. Harper Well # 1

Operator: Union Oil Company of Calif.

County Clark

Name & Address 2000 Classen Center So. Bldg.

Well Total Depth 5549 180.34 feet

Oklahoma City, OK 73106

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 532

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Good Well Service License Number 8343

Address Woodward, OK

Company to plug at: Hour: 7:30 am Day: 13 Month: September Year: 19 84

Plugging proposal received from Billy Nievar

(company name) Union (phone) 405-528-7601

were: 16" at 72' 5 1/2" at 5541 Perfs 5429-39 5445-51 5456-72 PBDT 5541

Set 5 1/2" cement retainer at 5338', Pressured up Morrow Perfs to 2000 psi. Would not take fluid. Pulled out of retainer & pumped 60 sx cement on retainer. Pulled above cement & circulated hole with 9.2 PPG plug mud. TOH w/tbg & setting tool. Perforated 5 1/2" casing at 936' and 5 1/2" and 10 3/4" casings at 100' Set 5 1/2" cement retainer at 500'. Set plug inside Plugging Proposal Received by Paul A. Luttich (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7:15 pm Day: 13 Month: September Year: 19 84

ACTUAL PLUGGING REPORT and outside 5 1/2" at 936-500' with 150 sx cement. P.O of

retainer and dumped 10 sx cement on top. TOH with setting tool. Circulated cement

through perfs at 100' out 5 1/2" x 10 3/4" and 10 3/4" x 16" annulus to surface with 55 sx cement. Did not get circulation between 10 3/4" and 16" - pressured up to 500 psi

and shut in. Cut-off head 5' below Ground level and welded on plate. SEP 17 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 9-20-84

Signed Paul A. Luttich (TECHNICIAN)

INV. NO. 3801