

1060340

15-025-10108-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

TECHNICIAN'S PLUGGING REPORT

C SW NW , SEC. 11 , T 34 S, R 21 W/E
3300 feet from N SE Corner of
4620 feet from W SE Corner of
NXX section line
NXX section line

Operator License # 5168

Lease Name K.C. Harper Well # 3

Operator: Union Oil Company of Calif.

County Clark

Name & Address 2000 Classen Center South Building

Well Total Depth 5508 179.01 feet

Oklahoma City, OK 73106

Conductor Pipe: Size feet

Surface Casing: Size 9 5/8 feet 584

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Good Well Service License Number 8343

Address Woodward, OK

Company to plug at: Hour: noon Day: 21 Month: September Year: 1984

Plugging proposal received from Billy Nievar

(company name) Union (phone) 405-528-7601

were: 5 1/2" set at 5508' Perfs at 5476-86 & 5494-98 PBD 5505'

1st plug plug off perfs through tubing at 5429' with 50 sx cement

2nd plug pull above cement and circulate hole with plug mud. Come out of hole with tubing

3rd plug perforate 5 1/2" casing at 930'. Circulate cement to surface via 9 5/8" x 5 1/2"

annulus with 265 sx cement, filling both pipes to surface.

Plugging Proposal Received by Paul A. Luttich (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:00 pm Day: 21 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 5508' Perfs at 5476-86 & 5494-98' PBD 5505'

1st plug plugged off perfs through tubing at 5429' with 50 sx cement, 2nd plug pulled

above cement and circulated hole with plugging mud. Came out of hole with tubing,

3rd plug perforated 5 1/2" casing at 930'. Circulated cement to surface via 9 5/8" x

5 1/2" annulus with 265 sx cement, filling both pipes to surface with cement.

Remarks: Used 60/40 Pozmix 2% gel by Halliburton

(If additional description is necessary, use BACK of this report)

RECEIVED
STATE CORPORATION COMMISSION

OCT 01 1984

10-01-84

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 10-8-84

INV. NO. 4118

Signed Paul A. Luttich (TECHNICIAN)