

1060336

15-025-10110-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 2-10-56

C SE NW, SEC. 11, T 34 S, R 21 W/4
3300 feet from ~~XXX~~ section line
3300 feet from ~~XXX~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5168

Lease Name K.C. Harper Well # 5

Operator: Union Oil Company of Calif.

County Clark

Name & Address 2000 Classen Center So. Bldg.

Well Total Depth 5518 179.34 feet

Oklahoma City, Ok 73106

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 580

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Good Well Service License Number 8343

Address Woodward, OK

Company to plug at: Hour: 1:00 pm Day: 17 Month: September Year: 19 84

Plugging proposal received from Billy Nievar

(company name) Union (phone) 405-528-7601

were: 5 1/2" set at 4418' PRTD 5484' Perfs 5454-66'

1st plug pump 50 sx cement through tubing at 4997'. Pull above cement & circulate hole with 9.0 PPg 36 Vis. plug mud. Perforate 5 1/2" csg. at 930' and circulate cement to surface via 9 5/8" x 5 1/2" annulus. Pump 250 sx cement through 5 1/2" casing filling 9 5/8" and 5 1/2" to surface. Cut off well heads and weld on plate.

Plugging Proposal Received by Paul A. Luttich (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:10 pm Day: 17 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4418' PRTD 5484' Perfs 5454-66'

1st plug pumped 50 sx cement through tubing at 4997'. Pulled above cement & circulated hole with 9.0 PPg 36 Vis. plug mud. Perf. 5 1/2" csg. at 930' & circulated cement to surface via 9 5/8" x 5 1/2" annulus. Pumped 250 sx cement through 5 1/2" casing filling 9 5/8" and 5 1/2" to surface. Cut off well heads and welded on plate.

Annulus shut in at 450 psi.

Remarks: Used Class H 60/40 with 2% gel. by Halliburton

(If additional description is necessary, use BACK of this form.)

(If possible, observe this plugging.)

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1984

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

DATE 10-2-84

Signed Paul A. Luttich (TECHNICIAN)

INV. NO. 3994