

1 050733

API NUMBER 15- 025-20,423 -00 -00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE SE, SEC. 12, T 34 S, R 21 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Operator: Hummon Corporation
Name & Address: 400 One Main Place
Wichita, KS 67202

660 feet from S section line

660 feet from E section line

Lease Name Hibbert Well # 1

County Clark 177.94

Well Total Depth 5475 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 608

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 West Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 30 Month: December Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" at 5460' PBD 5425' Perfs at 5400-5404'

1st plug sand back to 5350' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:35 am Day: 30 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 5350' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 300 psi

Remarks: Recovered 4400' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan. (If additional description is necessary, use BACK of this form.)

INVOICED (did not observe this plugging.)

STATE CORPORATION COMMISSION

Signed Richard W. Lucas (TECHNICIAN)

DATE JAN 06 1986

JAN 2 1986

INV. NO. 11843

CONSERVATION DIVISION

FORM CP-2/3 Rev. 01-84