

To: 1 051222  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7744

Operator: Sho-Bar Energy, Inc.  
Name:  
Address P.O. Box 217  
Harper, KS 67058

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547  
Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 20 Month: 10 Year: 19 89

Plugging proposal received from Kirby Lillard  
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 4400' PBSD 4343' Perfs at 4280-90' Elevation 1764' GL

1st plug pump 2 sx hulls and 25 sx cement to 4100',

2nd at 900' with 50 sx cement,

3rd plug at 400' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒

Operations Completed: Hour: 5 p.m. Day: 20 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 4100',

2nd plug at 900' with 50 sx cement,

3rd plug at 400' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3372' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If additional description is necessary, use BACK of this form.)

DATE 10-30-89

INV. NO. 26275  
10-20

10-20  
15-025-20673-00-00  
API NUMBER 15-025-20,663

SE SW SE, SEC. 15, T 34 S, R 21 W/E

330 feet from S section line

1650 feet from E section line

Lease Name Barby-Harper Well # 2-15A

County Clark 179.73

Well Total Depth 5530 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 854

OCT 24 1989

CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lacey  
(TECHNICIAN)