

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -025 20, 216-00-00

TECHNICIAN'S PLUGGING REPORT

990 FEET FROM ~~N/S~~ SECTION LINE Nw/4
1326 FEET FROM W/E SECTION LINE

OPERATOR LICENSE # 5654

LEASE NAME HARPER WELL # 1-17

OPERATOR: Rime Drilling Company
NAME & ADDRESS 300 west Douglas Suite 600
Wichita Kansas 67202

COUNTY CLARK
WELL TOTAL DEPTH 5500 \$178.75 FEET

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8 FEET 862

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Company Tools LICENSE NUMBER 5654

ADDRESS _____

COMPANY TO PLUG AT: HOUR: 1:00 pm DAY: 23 MONTH: August YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM _____

(COMPANY NAME) _____ (PHONE) _____

WERE: Use 60/40 Pos mix 2% Gal 3% cc.

Spot First Plug @ 900' w/50 sx cmt.; 2nd plug @ 450' w/25 sx cmt.;
3rd plug @ 40'-0 w/10 sx cmt. Circulate 10 sx cmt in Rat Hole
and 10 sx cmt in mouse hole.

PLUGGING PROPOSAL RECEIVED BY Steve Dorrant
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 4:00 pm DAY: 23 MONTH: August YEAR: 19 83

ACTUAL PLUGGING REPORT The following plugging was performed. Spotted
A plug @ 900' w/50 sx cmt.; A plug @ 250' w/25 sx cmt.; A plug @
40' w/10 sx cmt. I did circulate to top. The pusher Lee
Taylor would not put a solid bridge plug @ Forty Foot because
there was too much fluid in the hole according to him.
We put 15 sx cmt in Rat hole but it did not come to surface. 10 sx
was circulated in mouse hole. About 3' below ground level.

REMARKS: Halliburton did the cementing.

I (DID / ~~DID NOT~~) OBSERVE THIS PLUGGING.

INVOICED

DATE 8-26-83

INV. NO. 5363-W

SIGNED Benny E. Beck (TECHNICIAN) ✓

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-2/3
REV. 6-83

AUG 29 1983

CONSERVATION DIVISION
Wichita, Kansas