

1 051247

12-18

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,768 ~~0000~~

SE NE SE, SEC. 20, T 34 S, R 21 W/E
1650 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7744

Lease Name Barby-Harper Well # 1-20

Operator: Sho-Bar Energy, Inc.
Name & Address P.O. Box 217
Harper, KS 67058

County Clark 142.35
Well Total Depth 4380 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 850

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547
Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 18 Month: 12 Year: 19 89

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 5 1/2" at 4380' Perfs at 4264-68' Elevation 1773' GL

1st plug pump 2 sx hulls and 25 sx cement,
Spot through casing:
2nd plug at 880' with 50 sx cement,
3rd plug at 400' with 40 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 5 p.m. Day: 18 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 4200',
Spotted through casing:
2nd plug at 880' with 50 sx cement,
3rd plug at 400' with 40 sx cement,
4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1989
12-20-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3776' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

DATE 1-5-90

INV. NO. 26898 12-18