

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20466-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 21-34S-21W
1980 feet from N Section Line, 1980 feet from E Section Line
Lease/Unit Name: SHUPE Well Number: 2-21
County: CLARK Total Vertical Depth: 4400 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

Conductor Pipe Size: 20	feet: 111	WITH 350 SX CMT
Conductor Pipe Size: 13.375	feet: 320	WITH 250 SX CMT
Production Casing Size: 4.5	feet: 4389	WITH 175 SX CMT
Surface Casing Size: 8.625	feet: 844	WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/08/2003 1:25 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC. #143
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4200' WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/08/2003 2:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4366'. PERFS AT 4277-87'. SAND TO 4200' WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 800#.

RECEIVED
SEP 15 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3300' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)
INVOICED
DATE 9-15-03
WV. NO. 2004060501