

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20467-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 21-34S-21W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: BARBY Well Number: 4-21
County: CLARK Total Vertical Depth: 4400 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

Production Casing Size: 4.5 feet: 4383 WITH 175 SX CMT
Surface Casing Size: 8.625 feet: 864 WITH 800 SX CMT
143⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2003 11:10 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4200' WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/10/2003 11:45 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 4341'. PERFS AT 4269-79'. SAND TO 4200' WITH 4 SX CMT ON TOP. PUMPED 300# HULLS - 10 SX GEL - 5 SX CMT. SPLIT SURFACE PIPE FROM 0-2 1/2' AT 300#. 09/10/03: RAN TUBING TO 900'. SPOT 10 SX GEL & 50 SX CMT. PULL TO 400' & SPOT 40 SX CMT. PULL TO 40' & SPOT 10 SX CMT. HOLE STAYED FULL.

RECEIVED
5 2003
SEP 15 2003
WICHITA
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3100' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed _____

(TECHNICIAN)

INVOICED
DATE 9-15-03
INV. NO. 2004060501

Form SP-2/3