

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20483-00-00
Spot: CSENESE Sec/Twnshp/Rge: 21-34S-21W
990 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: BARBY Well Number: 5-21
County: CLARK Total Vertical Depth: 4400 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N. TYLER
WICHITA, KS 67212

Conductor Pipe: Size 20 feet: 95 \$ 143.00
Surface Casing: Size 8.625 feet: 809 WITH 800 SX CMT
Production: Size 4.5 feet: 4390 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/16/2002 12:20 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4250' WITH 4 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/16/2002 1:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4353'. PERFS AT 4292-98'. CIBP @ 4250' WITH 4 SX CMT ON TOP. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN PRESSURE 250#.


RECEIVED
AUG 20 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3000' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____



(TECHNICIAN)

INVOICED
DATE 8-21-02
BILL NO. 2003060302

AUG 16 2002

Form CP-2/3

