

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-20570-00-00  
Spot: NWSE Sec/Twnshp/Rge: 8-21S-33W  
2068 feet from S Section Line, 2022 feet from E Section Line  
Lease Name: ROSS-NEGELE Well #: 1  
County: FINNEY Total Vertical Depth: 4746 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4280		WITH 2 SX CMT
CIBP		4673		
PROD	5.5	4745	730	WITH 175 SX CMT
SURF	8.625	421		WITH 325 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2015 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/27/2015 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4280' WITH 2 SX CMT. 1/23/15: LOAD HOLE & RUN CBL FROM 2200' TO SURFACE. NO CEMENT BEHIND CASING. PUMP 25 SX PLUG DOWN 5 1/2" TO 2500'. 1/26/15: TAG TOC PLUG AT 2515'. PRESSURE TEST CASING TO 800#. HOLDING. BLOW COLLAR AT 2040'. SPOT 50 SX PLUG THROUGH BLOWN COLLAR HALF IN AND HALF OUT OF THE CASING. AFTER 2 1/2 HOURS TAG CMT @ 2009'. SDON. 1/27/15: PRESSURE TEST CASING TO 500#. HOLDING. BLOW A HOLE IN THE CASING AT 1180'. INJECTION RATE 1 BPM @ 300#. SPOT 50 SX CMT PLUG HALF IN & HALF OUT OF THE 5 1/2" CASING. BLOW A COLLAR @ 730' & PULL TO 460'. PUMP 50 SX CMT AT 460'. PUMP 10 SX CMT AT 40'.

Perfs:


Top	Bot	Thru	Comments
4690	4700		
4566	4610		
4330	4376		

Received  
KANSAS CORPORATION COMMISSION  
**FEB 12 2015**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed  (TECHNICIAN) 2/18/15 CKM

RECEIVED  
JAN 30 2015  
KCC DODGE CITY

Form CP-2/3