

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-01040-00-02
Spot: NWNWNE Sec/Twnshp/Rge: 6-34S-13W
344 feet from N Section Line, 2311 feet from E Section Line
Lease Name: OTT B Well #: 5-6
County: BARBER Total Vertical Depth: 5508 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		950		
CIBP		4130		WITH 2 SX CMT
PROD	5.5	5503	0	WITH 400 SX CMT
SURF	8.625	352		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/05/2015 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4800' WITH 2 SX CMT. PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/05/2015 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4130' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. (UNABLE TO GET CIBP ANY DEEPER). CUT 5 1/2" CASING AT 1943'. PIPE STUCK IN HOLE. SET CIBP @ 950'. LOAD HOLE WITH GEL & PRESSURE TEST 5 1/2" CASING TO 500#. PERFORATE 5 1/2" CASING AT 850'. PUMPED DOWN 5 1/2" CASING WITH 250 SX CMT. CMT DID CIRCULATE. 2/9/15: TOPPED OFF 5 1/2" CASING WITH 45 SX CMT & TOPPED OFF 5 1/2" X 8 5/8" ANNULUS WITH 35 SX CMT & PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4949	4966		
4874	4876		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 17 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Stephen Pfeifer (TECHNICIAN)
2/18/15 CKM
SP

RECEIVED
FEB 11 2015
KCC DODGE CITY