

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-179-21384-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 22-10S-30W  
2240 feet from N Section Line, 400 feet from E Section Line  
Lease Name: HAWKEYE Well #: 1-22  
County: SHERIDAN Total Vertical Depth: 4308 feet

Operator License No.: 34344  
Op Name: CULBREATH OIL & GAS COMPANY, IN  
Address: 3501 S YALE AVE  
TULSA, OK 74135

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	170		180 SX
SURF	8.625	305		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/05/2015 8:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: HAROLD BELERIVE Company: CULBREATH OIL & GAS COMPAN Phone: (918) 749-3508

Proposed Plugging Method: 8 5/8" surface casing set at 305' w/275 sx cement. 5 1/2" production casing set at 4297' w/170 sx cement. Port Collar set at 2443'. Port Collar was not cemented.  
Perforations: 3960' - 3963', 3978' - 3980' and 3994' - 3998'. RTD 4308'. Well non-commercial.  
Ordered 425 sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/05/2015 3:40 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Set CIBP at 3950' w/5 sx cement on top with dump bailer. Cut 5 1/2" casing at 2486'. Pulled casing to 2465' and pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled casing to 1475' and pumped 100 sx cement w/200 # hulls. Pulled casing to 355' and pumped 150 sx cement w/100 # hulls. 8 5/8" surface casing full.

GPS: 39.17051N -100.64822W

Perfs:

Top	Bot	Thru	Comments
3994	3998		
3976	3980		
3960	3963		

Remarks: GLOBAL CEMENT SERVICE TICKET # 1601

Plugged through: CSG

District: 04

Signed

Darrel Dipman  
(TECHNICIAN)

CM

2/18/15 CKM

FEB 06 2015

KCC WICHITA

FEB 13 2015

RECEIVED

Form CP-2/3