

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-22603-01-00  
Spot: NWSESESW Sec/Twnshp/Rge: 5-35S-3W  
365 feet from S Section Line, 2303 feet from W Section Line  
Lease Name: WILLEY Well #: 1-5  
County: SUMNER Total Vertical Depth: 4418 feet

Operator License No.: 32606  
Op Name: DEVON ENERGY PRODUCTION COMP  
Address: 333 W SHERIDAN AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	4570		
PROD	7	4936	648	495 SX
SURF	9.625	298		0 SX
T1	2.875	4550		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/08/2015 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: LARRY MASON Company: MASON PIPE & SUPPLY Phone: \_\_\_\_\_

Proposed Plugging Method: CIBP @ 3749' WITH 2 SXS. RECOVERED 7" FROM 648'. 50 SXS 650'. 135 SXS 350' TO 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/08/2015 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 3749' (TOP OF CURVE) & CAPPED WITH 2 SXS CEMENT. RECOVERED CASING FROM 648'. RAN TUBING TO 648' SPOTTED 50 SXS CEMENT. PULLED TUBING TO 350' & CIRCULATED WITH 135 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4970	8428		

KCC WICHITA

FEB 13 2015

RECEIVED

Remarks: EXCEL - COMMON - TMD = 8498

Plugged through: TBG

*[Signature]* 2/18/15 CKM.

District: 02

Signed \_\_\_\_\_  
(TECHNICIAN)