

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22767-00-00
Spot: NENESW Sec/Twnshp/Rge: 18-14S-18W
2378 feet from S Section Line, 2963 feet from E Section Line
Lease Name: MADDEN E F Well #: 2
County: ELLIS Total Vertical Depth: 3792 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3703		150 SX
SURF	8.625	249		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2015 8:00 AM
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING NELSON OIL CO. Phone: (785) 623-3290

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations- 3455' - 3620'. Fluid- 1400'. PBTD- 3544'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2015 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Nabors perforated at 1850', 1380' and 675'. Stewarts ran in hole with tubing to 3400' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1850' and pumped 130 sx cement to circulate cement to surface. Pulled tubing and topped off 4 1/2" casing with 25 sx cement. Hole standing full. Rigged to 8 5/8" surface casing and pumped 10 sx cement at 175 psi. Shut in pressured 175 psi.

GPS: 38.83380 -099.36739

Perfs:


Top	Bot	Thru	Comments
3602	3606		
3473	3482		
3455	3458		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1380

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

FEB 13 2015

RECEIVED