

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24180-00-00
Spot: NESESW Sec/Twnshp/Rge: 34-34S-3E
700 feet from S Section Line, 3280 feet from E Section Line
Lease Name: TAUSCHER Well #: 2
County: COWLEY Total Vertical Depth: 3345 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2106		100 SX
PROD	4.5	2206		100 SXS.
SURF	8.625	306		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/30/2015 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: GUS MYERS Company: ENDEAVOR ENERGY RESOURCES Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2015 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

1/29/2015 SET CIBP @ 1,875' CAPPED WITH 2 SXS OF CEMENT, THEN SHOT TWO PERORATION HOLES @ 360' RAN IN WITH TUBING TO 1700' PUMPED IN 50 SXS FOR BOTTOM PLUG, WITH A 469' OF BOTTOM PLUG, PUMPED 200 SXS FOR TOP PLUG, DID NOT GET THE RETURNS AND CIRCULATION NEEDED, RAN OUT OF CEMENT ON TRUCK. WILL COME BACK WITH AN ADDITIONAL 200 SXS ON TRUCK FOR NEXT MORNING. CONSOLIDATED OIL WELL SERVICES OUT OF CHANTUE, KS. FIRST TICKET #1014. CAME BACK NEXT MORNING 1/30/2015-RAN BACK IN 4.5" AND TAGGED TOP OF CEMENT @ 176' BULL-HEADED CASING AND PUMPED AN ADDITIONAL 40 SXS, PRESSURE HELD AND TOP PLUG COMPLETE. THEN RAN 1" POLY PIPE DOWN BACKSIDE OF 4.5" AND TAGGED CEMENT AT 250' SO AN TRADITIONAL 110 SXS WAS PUMPED DOWN THE BACKSIDE, PLUG JOB COMPLETE. CONSOLIDATED OIL WELL SERVICES SECOND CEMENT TICKET #1015.

Perfs:

Top	Bot	Thru	Comments
2032	2037	TBG	
1912	1920	TBG	
1752	1754	TBG	SPF

Remarks: WELL WAS PLUGGED UNDER A COMPLIANCE AGREEMENT COMMISSION ORDER 15-CONS-442-CMSC.

Plugged through: CSG

District: 02

Signed

[Signature]
(TECHNICIAN)

2/18/15 CKM

Received
KANSAS CORPORATION COMMISSION

FEB 12 2015

CONSERVATION DIVISION
WICHITA, KS