

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21364-00-00
Spot: NESWNE Sec/Twnshp/Rge: 19-34S-2E
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: THOMAS WILLIS T Well #: 1
County: SUMNER Total Vertical Depth: 3496 feet

Operator License No.: 32887
Op Name: ENDEAVOR ENERGY RESOURCES, LP
Address: 110 N MARIENFELD, STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3350		75 SX
SURF	8.625	261		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2015 11:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GUS MYERS & JOE DRISKI Company: ENDEAVOR ENERGY RESOURCES Phone: (918) 467-3111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/29/2015 11:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

1/28/2015-RAN IN WITH TUBING AND TAGGED SOMETHING HARD @ 300' RAN POWER SWIVEL AND DRILLED DOWN TO 420' RETURNS CAME BACK WITH A LOT OF METAL IN IT. OPERATOR DECIDED TO PLUG WELL. RAN IN WITH TUBING TO 420' AND PUMPED 210 SXS OF COMMON CEMENT WITH NO RETURN OF SLURRY BEFORE OPERATOR RAN OUT OF CEMENT ON TRUCK, WILL LET CEMENT SET UP TILL NEXT DAY AND TRY TO TAG TOP OF CEMENT. 1/29/2015 - RAN ALL THE WAY BACK IN WITH TUBING TO THE 420', SO PLUGGING OPERATOR BULLHEADED 4.5" CASING AND PRESSURED UP TO OVER 1100 PSIG WITH AN ADDITIONAL 40 SS, FOR TOP PLUG. PRES HELD AND TOP PLUG COMPLETE. CONSOLIDATED OIL WELL SERVICES OUT OF CHANUTE, KS. TICKET #1010 FOR THE 210 SX. AND 1011 FOR THE 40 ADDITIONAL SX.

Perfs:

Top	Bot	Thru	Comments
3212	3214	TBG	

Remarks: WELL WAS PLUGGED UNDER A COMPLIANCE AGREEMENT COMMISSION ORDER 15-CONS-442-CMSC

Plugged through: TBG

District: 02

Signed *Daniel Fox*
(TECHNICIAN)

KCC WICHITA

FEB 11 2015

RECEIVED