

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-24096-00-00
Spot: E2NWNSE Sec/Twnshp/Rge: 16-9S-22W
2310 feet from S Section Line, 665 feet from E Section Line
Lease Name: MCCALL B Well #: 1
County: GRAHAM Total Vertical Depth: 4010 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/04/2015 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix - 4% gel cement with 1/4# flo-seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 02/04/2015 7:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @3923 w/50 sx
2nd plug @1900 w/50 sx
3rd plug @1075 w/100 sx
4th plug @275 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx

Remarks: QUALITY

Plugged through: DP

2/18/15 CKM

District: 04

Signed _____

Case Morris
(TECHNICIAN)

KCC WICHITA

Form CP-2/3

FEB 06 2015

FEB 13 2015

RECEIVED