

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22350-00-00
Spot: NENE Sec/Twnshp/Rge: 3-34S-1W
440 feet from N Section Line, 620 feet from E Section Line
Lease/Unit Name: CHURCH Well Number: 1
County: SUMNER Total Vertical Depth: 4358 feet

Operator License No.: 31389
Op Name: NOBLE PETROLEUM, INC.
Address: 3101 N. ROCK ROAD, STE 125
WICHITA, KS 67226

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 393 240 SX CMT
Production: Size 5.5 feet: 4357 100 SX CMT 8/41.64
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 06/22/2001 10:45 AM
Plug Co. License No.: 9969 Plug Co. Name: KING'S WELL SERVICE LLC
Proposal Rcvd. from: GARY SHARP Company: NOBLE PETRO. INC. Phone: (316) 262-3596

Proposed Plugging Method: Perfs. 4346-4349. Sand 50' above perfs. And cap with 5sxs cement. Circulate cement from 440'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 06/22/2001 10:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP was set at 4300' and capped with 2sxs of cement. The 5 1/2" casing was recovered from 2500' and pulled to 460', where cement was circulated to surface. The remaining casing was pulled from the wellbore and the cement was topped off. (well was completed, but not commercial)


RECEIVED
KCC DISTRICT #2
JUN 26 2001
WICHITA, KS
INVOICED
DATE 7-3-01
INV. NO. 2002060003

Remarks: UNITED CEMENTING 60/40 4% GEL.

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)