

To: ² 100237
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-6-87
API NUMBER 15- 191-21,998-0000
NE, SEC. 9, T. 34 S, R 1 ~~WXXX~~
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3421
Operator: Simmons Energy Corporation
Name & Address 6464 S. Quebec
Englewood, CO 80111
(303) 796-9083

Lease Name Walcher Well # 1
County Sumner 145.44
Well Total Depth 4475 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Brandt Drilling Co., Inc. License Number 5840
Address _____

Company to plug at: Hour: 4:30pm Day: 6 Month: 7 Year: 1987

Plugging proposal received from _____
(company name) Brandt Drilling Co., Inc. (phone) _____

were: 35 sxs @1250, 35 sxs @430-440, 25 sxs 60w/plug, 10 sxs in rathole

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:15 Day: 6 Month: 7 Year: 1987

ACTUAL PLUGGING REPORT Fill hole with mud to 1250', spot 35 sxs cement. Pull pipe to
430' and spot 35 sxs cement at 60' on plug spot 25 sxs cement and put 10
sxs cement in rathole

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cemented #2461 60/40 poz 6% gel
(If additional description is necessary, use BACK of this form.)

INVOICED (If not observed, observe this plugging.)

Signed J. C. Sanders
(TECHNICIAN)

DATE 7-14-87
INV. NO. 17496