

Didn't have copy of Intent. to attach.

2 040177

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-191-21798-0000  
SEC. 13, T 34 S, R 1

TECHNICIAN'S PLUGGING REPORT

Operator License # 3601

Lease Name Wharry Well # 1

Operator: Associated Petro. Cons.

County Sumner 145.28

Name & Address One Main Place S# 600

Well Total Depth 4970 feet

Wichita Ks.

Conductor Pipe: Size \_\_\_\_\_ feet

67202

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Heartland Drilg Co. License Number 5867

Address One Main Place S# 600 Wichita Ks.

Company to plug at: Hour: 2200 Day: 19 Month: 3 Year: 19 85

Plugging proposal received from Jack Kaiser

(company name) Heartland Drilg Co. (phone) \_\_\_\_\_

were: 40sx 1350

35sx 310

25sx 60

10 sx RH

10 sx MH.

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2300 Day: 19 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Run Drill pipe to 1350' and circulate hole full of good mud. spot 40 sack of Cement at 1350' and displace with mud. Pull Drill Pipe to 310' fill hole with Mud and spot 35 sack of cement. Pull Pipe to 60' and Circulate the hole full with 25 sack of Cement. Circulate 10 sacks of cement in the Rat Hole and 10 sacks

Remarks: of cement in the mouse hole. By Sun Cementing. If additional description is necessary, use BACK of this form.) #206458

INVOICED

DATE 4/4/85

INV. NO. 7570

3.19

I, ~~did~~ did not observe this plugging.

MAR 26 1985

Signed Steve Green (TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

RC