

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

5-20

API NUMBER: 15-191-22337 - 0000

140' S & 110' W C-E/2-NE-NW SECTION 15 TOWNSHIP 34 RANGE 1W

OPERATOR LICENSE # 31389 4480 FEET FROM S SECTION LINE
OPERATOR Noble Petroleum INC. 3080 FEET FROM E SECTION LINE
NAME 3101 N. Rock Road # 125
ADDRESS Wichita KS. 67226 LEASE NAME: McKinney #1
COUNTY Sumner
WELL TOTAL DEPTH: 4510 146.58
PIPE: _____
SURFACE CASING 8 5/8 @ 250'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Duke Drilling
ADDRESS: Wichita, KS LICENSE: 5929

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: _____

PLUGGING PROPOSAL RECEIVED FROM: Rich Wheeler
COMPANY NAME: Duke Drilling PHONE: 316-267-1331
WERE: 35 sks at Arbuckle 15 sks in Rathole
35 sks at 1000
35 sks at 500
35 sks at 300
25 sks at 60

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 02 1999

CONSERVATION DIVISION
WICHITA KS

PLUGGING PROPOSAL RECEIVED BY: R. Title

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (X)
COMPLETED: HOUR: 1400 DAY: 20 MONTH: 5 YEAR: 1999

ACTUAL PLUGGING REPORT: The drill pipe was run to 4474', where 35 sks of cement was spotted over the Arbuckle. The drill pipe was pulled to 1000' where 35 sks. Of cement was spotted. The drill pipe was pulled to 300' where 25 sks of cement was spotted. The drill pipe was pulled to 60' where cement was circulated to surface. The Rathole was circulated with 15 sks of cement.

REMARKS: Allied Cementing 60/40 Poz 4% gel

I DID NOT OBSERVE THIS PLUGGING.

[Signature]
Steve Vandfieson

FORM CP-2/3
REV. 3/90

INVOICED

DATE 6-3-99
INV. NO. 61003