



15-025-10129-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of McAdams has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: McAdams Pipe & Supply Company

Complete Address: Drawer 960, Bristow, Oklahoma 74010

Lease Name: R.S. Shupe "A" Well No. 1

Location: C NE NW Sec. 21 Twp. 34 Rge. 21 (E) (W)

County: Clark Total Depth 5555' Oil Well X

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

20" to 78' circulated w/ cement. 13 3/8" to 597' circulated w/ cement.

8 5/8" to 1568' cemented. 5 1/2" to 5533' cemented.

Top perforations 5395' Plug bottom w/ 20 sacks cement.

Top of cement 5300' Mud 5300' to 590'

Spot 50 sacks cement 590' to 510' Mud 510' to 30'

Plug, Hulls & 15 sacks cement 30' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent