



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

16 April 1982

RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1982

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)  
15-025-20583-00-00

Dear Sir:

Mr. Jerry Young of Rine Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Rine Drilling Co.

Complete Address: Suite 600, 300 West Douglas, Wichita, Kansas 67202

Lease Name: Barbey - Harper Well No. 7-21

Location: NW-SE-NW Sec. 21 Twp. 34 Rge. 21 (E) (W)

County: Clark Total Depth: 4320'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Young was instructed to plug the well as follows:

They set 850' of 8 5/8" surface casing cement circulated. The anhydrite was topped at 1200'; 1st plug at 1200' with 70 lbs of cement. 2nd plug at 875' with 35 lbs of cement. 3rd plug on solid bridge at 40' to 0' with 10 lbs of cement. Then circulated 10 lbs in rat hole & 5 lbs of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The cementing was accomplished by Halliburton Co.

Very truly yours,

Paul A. Luttich  
Conservation Division Agent