

State of Kansas



FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Morgenstern & Spector Inc.

Complete Address: P. O. Box 661. Russell, Kansas

Lease Name: Armistead "B" Well No. # 1

Location: NW SW NW Sec. 2 Twp. 28 Rge. 11 (E) (W) W

County Pratt Total Depth 4183 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Lynch was instructed to plug the well as follows:

376' of 8 5/8" surface pipe, cement circulated. 4163' of 5 1/2"  
long string, cemented with 165 sacks. Sand to 4150', cement  
with 5 sacks. Fill hole with mud to 250', 10' rock bridge,  
cement with 20 sacks. Fill hole with mud to 40', 10' rock  
bridge, cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
Conservation Division Agent