

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-23715-00-00
Spot: NESENE Sec/Twnshp/Rge: 4-15S-14W
675 feet from N Section Line, 250 feet from E Section Line
Lease Name: DRISCOLL-MAIER UNIT Well #: 1
County: RUSSELL Total Vertical Depth: 3272 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3270	1990	155 SX
SURF	8.625	324		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/27/2015 1:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-1683

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2015 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

01/26/2015- Sanded off to 2850' and dumped 5 sx of cement on top.
01/27/2015- Cut casing at 1990'. Pulled casing to 1520' and pumped 125 sx cement w/300 # hulls. Pulled casing to 770' and pumped 50 sx cement w/50 # hulls. Pulled casing to 350' and pumped 85 sx cement. Cement circulated to cellar. POOH and cellar stayed full of cement. Total of 45 joints of 5 1/2" casing was pulled out of well.

GPS: 38.78186 -098.87447

Perfs:

Top	Bot	Thru	Comments
3208	3210		
3206	3208		
3202	3210		
2958	2996		

Remarks: QUALITY CEMENTING TICKET # 1203

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

2/18/15 CKM

FEB 06 2015

KCC WICHITA

Form CP-2/3

FEB 13 2015

RECEIVED