

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-023-20369-00-00  
Spot: W2SESE Sec/Twnshp/Rge: 30-2S-41W  
610 feet from S Section Line, 1210 feet from E Section Line  
Lease Name: MYERS TRUST Well #: 1-30X  
County: CHEYENNE Total Vertical Depth: 5062 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 5042       |             | 275 SX   |
| SURF   | 8.625 | 387        |             | 275 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/02/2015 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 269-7290

Proposed Plugging Method: 8 5/8" surface casing set at 387' w/275 sx cement. 4 1/2" production casing set at 5042' w/275 sx cement. TD 5062'. PBTD 4730' w/ bridge plug. Perforations: 4576' - 4580', 4646' - 4656' and 4796' - 4800' below bridge plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/02/2015 6:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

2 3/8" tubing stuck in 4 1/2" casing. Cut tubing at 4480'. Perforated production casing at 3643' and 2900'. Ran tubing to 4416' and pumped 25 sx cement without hulls and 75 sx cement w/200 # hulls. Pulled tubing to 2975' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1503' and pumped 150 sx cement w/150 # hulls. CWC. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 25 sx cement. Connected to 8 5/8" surface casing and pumped 75 sx cement. Shut in pressure 50 psi.

GPS: 39.84510N -101.95995W

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4796 | 4800 |      |          |
| 4646 | 4656 |      |          |
| 4576 | 4580 |      |          |

Remarks: SWIFT CEMENT TICKET # 26,995 JUNK IN HOLE FROM 4480' TO 4688'.

Plugged through: TBG

*2/18/15 CKM*

District: 04

Signed Darrel Dipman  
(TECHNICIAN)  
KCC WICHITA

*CM*

FEB 13 2015

Form CP-2/3

FEB 06 2015

RECEIVED